



COUNTY OF SANTA CLARA
Santa Clara Valley Health and Hospital System

ADDENDUM

Addendum #4

Modify Summary of Work Section 01110

Summary of work

The scope of Work of this Contract consists of, but not limited, to the following:

Provide horizontal structured cabling infrastructure as indicated on the constructions documents. Scope includes horizontal cabling, terminations, labeling, testing, etc. The contractor is responsible for outlet/device counts as shown on the construction documents.

Provide secondary pathways (cable hangers) as required for station cabling support from the existing cable tray to the existing device conduit.

Provide backbone cabling between MDF and each IDF room composed of singlemode and multimode fiber optic and CAT3 and CAT5e UTP cabling. Scope includes backbone cables, termination, labeling, testing etc. The contractor is responsible for cable types and quantities as shown on the construction documents.

Partial build-out of telecom rooms with telecom components. The building contains one MDF room on the first floor and one IDF room on first, second, and third floors. The partial build-out includes but not limited to equipment racks and cabinets, 110-blocks wall termination field, cable and wire managers, vertical cable runway, bonding, labeling, etc.

Install owner provided wireless access units adjacent to WAP type outlets.

Provide cross-connects for building systems such as fire alarm, elevators controls, BMS, and security system.

Coordinate MPOE installation with AT&T. Extend the MPOE copper services from the AT&T demarc to the owner 110 wall field.

The construction drawings (TC set) and specification (167xx) will govern quantities, types, and installation methods for this telecommunications work.