

The project proposal includes:

1. Removal of approximately 1760 cy of stockpiled materials brought to the site in 2018, including turf strippings, cobbles and soil, bunker sand, gravel base and top soil.
2. Removal of up to 10,000 cy of soil, thereby removing the net fill imported to the site between 2000 and 2017. Re-contouring of the site to match and conform to 2000 contours to the extent feasible, while also implementing recommendations by the professional arborist for protection of existing onsite trees and future geotechnical recommendations to ensure slope stability and prevent erosion. All trees within the project boundary will be protected with contours within the tree protection zones to remain at 2017 condition, and no trees are proposed for removal.

Vegetation material from golf course landscape maintenance and straw that is currently stockpiled on the site will be chipped and used as mulch and edge dressing respectively. The site will be hydro seeded and restored to a natural-looking state.