

# **County of Santa Clara**

## **Sixteenth Amendment to the Countywide Nondisposal Facility Element**

**March 2016**

**CalRecycle Review & Approval**

**Submitted: March 2016**

**Approved:**

**SIXTEENTH AMENDMENT TO THE COUNTY OF SANTA CLARA  
COUNTYWIDE NONDISPOSAL FACILITY ELEMENT**

The Countywide Nondisposal Facility Element (NDFE) was originally adopted by the Board of Supervisors on December 13, 1994. The First Amendment was adopted on June 3, 1997, replacing and superseding the original document. The Second Amendment was adopted on August 5, 1997, and it replaced and superseded the NDFE and the First Amendment. On September 15, 1998, on December 7, 1999, on May 9, 2000, on December 13, 2003, on August 25, 2009, on February 23, 2010, on March 15, 2011, on November 11, 2011, the Third, Fourth, Fifth, Sixth, Seventh, Eighth, Ninth and Twelfth Amendments were adopted. Following revised adoption rule, the Thirteenth Amendment, the Fourteenth Amendment and the Fifteenth Amendment were updated by CalRecycle in January 2014, March 2014 and June 2014. This NDFE may be adopted by other jurisdictions.

**TABLE OF CONTENTS**

<b>Introduction (Sixteenth Amendment - revised 03 /16)</b>	1
<b>City of Palo Alto Green Composting Facility (Sixth Amendment 12/03 - revised)</b>	
Map: City of Palo Alto Green Composting Facility	2
Fact Sheet #1: Palo Alto Green Composting Facility	3
<b>Guadalupe Landfill</b>	
Map: Guadalupe Landfill	4
Fact Sheet #2: Guadalupe Landfill	5
<b>Material Recovery Systems Facility</b>	
Map: Material Recovery Systems Facility	6
Fact Sheet #3: Material Recovery Systems Facility	7
<b>Newby Island Compost Facility (Seventh Amendment 8/09 – revised)</b>	
Map: Newby Island Compost Facility	8
Fact Sheet #4: Newby Island Compost Facility	9
<b>Zanker Materials Processing Facility (Sixth Amendment 12/03 - revised)</b>	
Map: Zanker Materials Processing Facility	10
Fact Sheet #5: Zanker Materials Processing Facility	11
<b>The Recyclery at Newby Island (Seventh Amendment 8/09 – revised)</b>	
Map: The Recyclery at Newby Island	12
Fact Sheet #6: The Recyclery at Newby Island	13
<b>San Martin Transfer Station (Sixth Amendment 12/03 – revised, Twelfth Amendment 08 /11 – revised)</b>	
Map: San Martin Transfer Station	14
Fact Sheet #7: San Martin Transfer Station	15
<b>Sunnyvale Materials Recovery and Transfer Station (SMaRT) Station</b>	
Map: SMaRT Station	16
Fact Sheet #8: SMaRT Station	17
Exhibit A	18

<b>Zanker Road Class III Landfill (Sixth Amendment 12/03 - revised)</b>	
Map: Zanker Road Class III Landfill	19
Fact Sheet #9: Zanker Road Class III Landfill	20
<b>Dunne Ranch Compost Facility (Pages 21, 22) has been deleted (Fourth Amendment 12/99)</b>	
<b>Z-Best Composting Facility</b>	
Map: Z-Best Composting Facility	23
Fact Sheet #11: Z-Best Composting Facility	24
<b>GreenWaste Recovery Facility (Third Amendment 9/98 - added, Fourth Amendment 12/99 - revised)</b>	
Map: GreenWaste Recovery Facility	25
Fact Sheet #12: GreenWaste Recovery Facility	26
<b>ComCare Farms Composting Facility (pages 27-28) has been deleted (Eighth Amendment 2/10)</b>	
<b>South Valley Organics (Fourth Amendment 12/99 – added, Sixth Amendment 12/03 – revised, Twelfth Amendment 08 /11 – revised)</b>	
Map: Pacheco Pass Landfill Composting Facility	29
Fact Sheet #14: South Valley Organics	30
<b>Butterick Enterprises Recyclery</b>	
Map: Butterick Enterprises Recyclery	31
Fact Sheet #15: Butterick Enterprises Recyclery	32
<b>Premier Recycling Facility (Fifth Amendment 5/00 - added)</b>	
Map: Premier Recycling Facility	33
Fact Sheet # 16: Premier Recycling Facility	34
<b>Environmental Management Systems Facility (pages 35-36) has been deleted (Seventh Amendment 8/09)</b>	
<b>California Waste Solutions Recycling &amp; Transfer Station (Sixth Amendment 12/03 - added)</b>	
Map: California Waste Solutions Recycling & Transfer Station	37
Fact Sheet # 18: California Waste Solutions Recycling & Transfer Station	38
<b>Pacific Coast Recycling, Inc. Facility (Sixth Amendment 12/03 - added)</b>	
Map: Pacific Coast Recycling, Inc. Facility	39
Fact Sheet # 19: Pacific Coast Recycling, Inc. Facility	40
<b>Pacheco Pass Transfer Station (Seventh Amendment 8/09 – added, Twelfth Amendment 08/11 – revised)</b>	
Map: Pacheco Pass Transfer Station	41
Fact Sheet # 20: Pacheco Pass Transfer Station	42
<b>Stanford Recycling Center and Direct Transfer Facility (Seventh Amendment 8/09 - added)</b>	
Map: Stanford Recycling Center and Direct Transfer Facility	43
Fact Sheet # 21: Stanford Recycling Center and Direct Transfer Facility	44
<b>GreenTeam of San Jose Material Recovery Facility and Transfer Station (Eighth Amendment 2/10 - added)</b>	
Map: GreenTeam of San Jose Material Recovery Facility and Transfer Station	45
Fact Sheet # 22: GreenTeam of San Jose Material Recovery Facility and Transfer Station	46

<b>GreenWaste Material Facility and Transfer Station (Eighth Amendment 2/10 - added)</b>	
Map: GreenWaste Material Facility and Transfer Station	47
Fact Sheet # 23: GreenWaste Material Facility and Transfer Station	48
<b>Recology Silicon Valley Processing and Transfer Facility (Ninth Amendment 3/11 - added)</b>	
Map: Recology Silicon Valley Processing and Transfer Station	49
Fact Sheet # 24: Recology Silicon Valley Processing and Transfer Facility	50
<b>Zero Waste Energy Development Company Anaerobic Digestion Facility (Ninth Amendment 3/11 - added)</b>	
Map: Site Location – 9 Par Landfill Site	51
Map: Site Vicinity Map – 9 Par Landfill Site	52
Fact Sheet # 25: Zero Waste Energy Development Company’s Anaerobic Digestion Facility	53
<b>Green Earth Management LLC Kings Row Recycling Facility (Ninth Amendment 3/11 - added)</b>	
Map: 650 Kings Row	54
Fact Sheet # 26: Green Earth Management LLC Kings Row Recycling Facility	55
<b>Environmental Resource Recovery, Inc., (Valley Recycling) (Ninth Amendment 3/11 - added)</b>	
Map: Site Location Map – Valley Recycling	56
Fact Sheet # 27: Environmental Resource Recovery, Inc., DBA Valley Recycling	57
<b>Smurfit-Stone Recycling San Jose Facility (Ninth Amendment 3/11 - added)</b>	
Map: Smurfit-Stone Recycling San Jose Facility Location Map	58
Fact Sheet # 28: Smurfit-Stone Recycling San Jose Facility	59
<b>Wood Processing Facility at Recology Pacheco Pass (Twelfth Amendment 08/11 - added)</b>	
Map: Wood Processing Facility at Recology Pacheco Pass Facility Location Map	60
Fact Sheet # 29: Wood Processing Facility at Recology Pacheco Pass	61
<b>Valley Recycling San Jose CDI Processing/Transfer Facility (Thirteenth Amendment 01/14 - added)</b>	
Map: Valley Recycling San Jose CDI Processing/Transfer Facility Location Map	62
Fact Sheet # 30: Valley Recycling San Jose CDI Processing/Transfer Facility	63
<b>Mission Trail Food Materials Transfer/Processing Operations (Fourteenth Amendment 03/14 - added)</b>	
Map: Mission Trail Food Materials Transfer/Processing Operations Location Map	64
Fact Sheet # 31: Mission Trail Food Materials Transfer/Processing Operations	65
<b>ECO Box Recycling, Inc. (Fifteenth Amendment 06/14 - added)</b>	
Map: ECO Box Recycling, Inc. Location Map	66
Fact Sheet # 32: ECO Box Recycling, Inc.	67
<b>Leo Recycle (Sixteenth Amendment 03/16 - added)</b>	
Map: Leo Recycle Location Map	66
Fact Sheet # 33: Leo Recycle	67

**SIXTEENTH AMENDMENT TO THE  
COUNTY OF SANTA CLARA  
COUNTYWIDE NONDISPOSAL FACILITY ELEMENT**

**Introduction**

California Public Resources Code (PRC) Sections 41730 et seq., require California cities and counties to prepare and adopt a Nondisposal Facility Element (NDFE) for all existing or proposed nondisposal facilities which will be needed to implement local Source Reduction and Recycling Elements. A nondisposal facility is any solid waste facility required to obtain a solid waste facility permit except a disposal facility or transformation facility (PRC Section 40151).

In 1994, the County of Santa Clara's Integrated Waste Management Program prepared the Countywide NDFE for adoption by the cities of: Campbell, Cupertino, Gilroy, Los Altos, Milpitas, Monte Sereno, Morgan Hill, Mountain View, San Jose, Santa Clara, Saratoga, and Sunnyvale; the towns of Los Altos Hills and Los Gatos; and the County of Santa Clara Unincorporated Area. The City of Palo Alto prepared and adopted its own NDFE. In March 1997, the First Amendment to the Countywide NDFE was prepared by the IWM Program for use by jurisdictions as necessary. The Second Amendment was approved in July 1997; the Third in September 1998; the Fourth in December 1999; the Fifth in May 2000; the Sixth in December 2003; the Seventh in August 2009; and the Eighth in February 2010; and the Ninth Amendment (which was a collection of the Ninth, Tenth and Eleventh combined) in March 2011; and the Twelfth Amendment in November 2011. With the change in amending NDFEs pursuant to AB341 (Chapter 4.5, Statutes of 2011, Chesbro, AB341), CalRecycle updated the NDFE to include the Thirteenth in January 2014; the Fourteenth in March 2014; and the Fifteenth in June 2014.

The Countywide NDFE identifies transfer stations, material recovery facilities, yard waste composting facilities, and landfills necessary to implement local waste diversion goals.


**The Sixteenth Amendment to the Countywide NDFE**

Leo Recycle is in the process to apply for a Registration Tier permit from the City of San Jose Local Enforcement Agency (LEA). This Sixteenth Amendment to the Countywide NDFE (Amendment) is necessary in order for the LEA to find the proposed facilities in conformance and for the permit applications to be accepted as complete.

Maps and fact sheets for these facilities are attached as pages 68 – 69 of the amended NDFE.

Due to the change in amending NDFEs pursuant to AB341 (Chapter 4.5, Statutes of 2011, Chesbro, AB 341) there are no longer specific regulatory requirements for public noticing or approval that a jurisdictions must follow. As indicated by PRC Section 41735 (a), adoption of the Amendment is not subject to environmental review under the California Environmental Quality Act (CEQA). The Amendment supersedes and replaces the Fifteenth Amendment as the NDFE for the County of Santa Clara Unincorporated Area. It may be adopted by other jurisdictions.

FIGURE 1



DRAWN BY:  
 DATE:  
 CHECK'D BY:  
 DATE:

GREEN COMPOSTING FACILITY  
 LOCATION MAP

APPROVED BY:  
 PE NO. \_\_\_\_\_  
 DATE: \_\_\_\_\_

SCALE: NONE

City of Palo Alto

DRAWING NO.

**Fact Sheet #1  
City of Palo Alto Green Composting Facility  
Palo Alto, California**

**TYPE OF FACILITY:**

The Palo Alto Green Composting Facility (Facility) is owned and operated by the City of Palo Alto (City). The Facility began operation in 1977 with the goal of extending the life of the Palo Alto Landfill by diverting yard waste brought to the landfill. The Facility accepts yard waste from City residents, non-residents, private gardeners, City crews, tree and landscape contractors working for the City, and county and state crews working on freeway landscaping within City limits. In 1990, the City began operating a full-scale curbside yard waste collection program for its residents. Acceptable yard waste includes leaves, grass clippings, plant and shrub trimmings, ivy, and tree parts. Once delivered to the Facility, the yard waste is ground up, cured in windrows, screened after completion; and stored on-site before being transported to markets. The finished compost is used as a topsoil amendment in the City's landfill closure and is being sold to nurseries on the open market for retail sale to the public.

**FACILITY CAPACITY:**

15,211 tons per year of green waste were accepted for processing at the Facility during 2001. In accordance with the Facility's standardized composting facility permit, it has an estimated annual operation capacity of 17,000 tons (about 47 tons per day) with a peak loading capacity of 130 tons per day.

**ESTMATED DIVERSION RATE:**


In 2001, total waste generated in the City was 197,130 tons. Based on these figures, the 2001 diversion rate for the facility was approximately 8% of the total City waste stream.

**JURISDICTIONS SERVED:**

The Facility serves the County of Santa Clara. However, the Facility is primarily used by residents, businesses, and organizations that reside within the City of Palo Alto's limits.

**FACILITY LOCATION:**

The Facility is located in Santa Clara County within the footprint of the City of Palo Alto Landfill at 2380 Embarcadero Road, Palo Alto (see the attached map).



Highway 85 Corridor

Project Site

**Fact Sheet #2**  
**Guadalupe Landfill**  
**Material Recovery and Compost Processing Facility**  
**San Jose, California**

**TYPE OF FACILITY:**

The Guadalupe Landfill (Facility) is owned and operated by Guadalupe Rubbish Disposal Company, Incorporated. The Facility began operations as a sanitary landfill in 1956. The permitted Class III landfill has ongoing material recovery and compost processing operations. The Facility receives waste from all over Santa Clara County. Material recovery operations are conducted on the active face of the landfill. The composting processing facility area is currently undergoing environmental review and permitting procedures. The proposed compost facility would consist of a 7-acre yard and wood waste processing area and an 11-acre windrow composting area. The Facility currently accepts yard waste and clean wood waste from residential self-haulers, gardeners and landscapers, governmental landscape maintenance and road crews, and franchised and non-franchised municipal waste haulers. Once delivered to the Facility, yard waste is ground up and sold immediately to land application markets. The proposed compost facility permit would allow yard waste to be ground up, cured aerobically in windrows, screened after completion, and transported to markets. Wood waste is kept separate, ground up, and transported to wood fuel markets. All materials are received on a tipping fee basis. The Facility also recycles construction and demolition debris (soil, concrete, and asphalt) which is used on-site as construction materials and daily landfill cover.

**FACILITY CAPACITY:**

The Facility has a maximum permitted disposal capacity of 3,375 tons per day. In 1993, the Facility landfilled approximately 356 tons per day. In the currently proposed permit, the maximum processing capacity of the compost facility is 672 tons of yard and wood waste per day.

**ESTMATED DIVERSION RATE:**



In 1993, the Facility had a diversion rate of approximately 39.6% (129,919 tons of the 328,361 tons received at the landfill gate).

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County.

**FACILITY LOCATION:**

The Facility is located in Southwestern San Jose, off Guadalupe Mines Road, in a canyon immediately north of Guadalupe Mines (see the attached map).



MISSION TRAIL WASTE SYSTEMS  
 1100 RICHARD AVENUE  
 SANTA CLARA, CALIFORNIA

---

SITE LOCATION MAP

FIGURE  
**2**  
 PROJECT NO.  
 479-02.02

**Fact Sheet #3  
Material Recovery Systems Facility  
Santa Clara, California**

**TYPE OF FACILITY:**

The Material Recovery Systems Facility (Facility) is owned by Rinauro Investment Properties and operated by Material Recovery Systems Incorporated. The Facility began operation in December of 1991. The Facility is a permitted 21,252 square foot (half-acre) transfer station that began operation in December of 1991. Prior to August 1996, the Facility received material from the City of Santa Clara's (City) curbside residential and multi-family recycling programs, the general public and commercial business. The Facility currently receives and processes recyclable materials from commercial/industrial businesses and the general public. The Facility accepts the following materials: construction and demolition debris, wood waste, glass, metals, plastics, paper, and any other commercial and industrial solid wastes. Materials are conveyer-fed through a sorting line and into a conveyer-fed baler. Materials recovered are shipped to brokers and markets which use them for manufacturing into new products. Residual materials and debris are transported and landfilled at a permitted facility.

**FACILITY CAPACITY:**

The Facility is permitted to process a maximum of 375 tons of waste per day. The Facility currently processes an average of 80 tons per day.

**ESTMATED DIVERSION RATE:**

The current diversion rate for the Facility is approximately 20%. Prior to August 1996 the Facility had a diversion rate of approximately 40%.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County.

**FACILITY LOCATION:**

The Facility is located at 1060 Richard Avenue, in an industrially zoned area of the City of Santa Clara (see the attached map). The Facility can be accessed from either 1060 Richard Avenue or 1313 Memorex Drive in Santa Clara.

(TO FREMONT)

(TO PLEASANTON)



880

680

WARM SPRINGS CREEK RD.

SCOTT

FREMONT CITY LIMIT  
MILPITAS CITY LIMIT

DIXON LANDING ROAD

MILPITAS BLVD.

COMPOSTING  
FACILITY SITE  
LOCATION

JACKLIN ROAD

MILPITAS

680

SAN JOSE CITY LIMITS  
MILPITAS CITY LIMIT

880

237

237

GRAPHIC SCALE



( IN FEET )

(TO SAN JOSE)

**JAMES A. WYSE INC.**  
WASTE MANAGEMENT CONSULTANTS

NEWBY ISLAND RECYCLERY  
BROWNING-FERRIS INDUSTRIES, INC.  
SAN JOSE, CALIFORNIA

SITE LOCATION MAP

FIGURE  
**1**  
PROJECT NO.  
130-1.3

City of Milpitas, 10/18/90, 10/18/90, 10/18/90

**Fact Sheet #4**  
**Newby Island Compost Facility**  
**San Jose, California**

**TYPE OF FACILITY:**

The Newby Island Compost Facility (Facility) is owned and operated by Browning Ferris Industries. The permitted Facility began operation in 1994, and consists of a 2-acre pre-processing area and a 10-acre windrow composting pad. The Facility accepts yard waste and clean wood waste from residential self-haulers, private gardeners and landscape contractors, municipal and state government landscape maintenance and road crews, and franchised and non-franchised municipal yard waste haulers. Once delivered to the Facility, yard waste is ground up, cured aerobically in windrows, screened after completion, and transported to markets. Some yard waste is ground up and sold immediately to land application markets. Wood waste is kept separate, ground up, and transported to wood fuel markets.

**FACILITY CAPACITY:**

The Facility is permitted to process a maximum of 500 tons of yard and wood waste per day. The Facility is currently processing approximately 300 tons of yard and wood waste per day.

**ESTMATED DIVERSION RATE:**

The Facility is currently diverting 99% (approximately 297 tons per day) of the material received for processing.


**JURISDICTIONS SERVED:**

The Facility currently serves all of Santa Clara County and portions of Alameda, Contra Costa and San Mateo counties. The Facility processes curbside yard waste for several jurisdictions in Santa Clara County.

**FACILITY LOCATION:**

The Facility is located adjacent to the Newby Island Landfill and the Recyclery at Newby Island, at 1601 Dixon Landing Road in north San Jose, just west of Highway 880 (see the attached map).

FIGURE I-5 -- SITE LOCATION AND VICINITY ROADWAYS



**Fact Sheet #5**  
**Zanker Material Processing Facility**  
**San Jose, California**

**TYPE OF FACILITY:**

The Zanker Material Processing Facility (Facility) is a resource recovery and landfill site located at 675 Los Esteros Road in San Jose, California. The 46-acre landfill site is located on an 88-acre parcel of land previously owned by Owens Corning Fiberglas Corporation. The site was used exclusively since 1956 for the disposal of manufacturing wastes from the Owens Corning manufacturing plant in Santa Clara, California. Zanker Road Resource Management, Ltd. (ZRRML) is currently the operator of the Facility on the site.

The site had historically been designated as a “candidate solid waste facility” and a “nonconforming land use” by the City of San Jose (City). In September of 1996, the City rezoned the property from M-1 (light manufacturing) to PD (planned development) to allow for the siting of the Facility. The City also certified an environmental impact report for the Facility, completing the environmental review process. ZRRML has obtained permits for the Facility from the City Department of Planning, Building, and Code Enforcement, the California Integrated Waste Management Board, the San Francisco Bay Regional Water Quality Control Board, and the Bay Area Air Quality Management District. The Facility has been in operation since 1999.

The Facility includes resource recovery operations for processing mixed construction and demolition material into secondary products such as road base, biomass fuel, landscape products (wood chips, wood fines, etc.), as well as metals, cardboard, and clean fill. The facility is open to the public for receipt of waste material and for the sale of finished products.

**FACILITY CAPACITY:**

The Facility has a permitted gate capacity of 1,250 tons per day, and a maximum disposal capacity of 350 tons per day. It is estimated that the Facility landfills an average of 65 tons per day.

**ESTIMATED DIVERSION RATE:**


The Facility diverts, on an average, more than 85 percent of waste accepted at the gate.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County and all neighboring counties.

**FACILITY LOCATION:**

The Facility is located at 675 Los Esteros Road in north San Jose, near the Zanker Road Landfill and the San Jose/Santa Clara Water Pollution Control Plant (see the attached map).



SCALE  
0 10 20 30 40 50 60 70 80 90 100

**SITE CIRCULATION PLAN**

**VEHICULAR CIRCULATION INDEX**

- PUBLIC / TRUCKS VEHICLES
- CONVENTIONAL, RECREAL TRUCK TRAFFIC
- SPECIAL PURPOSE TO REMOVE DIRT
- BICYCLES - P. TRAILING, RECREATION
- PEDESTRIAN CIRCULATION (BY ROAD, SIDEWALK, PATH, BRIDGE, ETC.) FOR ACCESS TO ALL FUNCTIONS

REV 9/10

<b>PD 3A</b> Project No. 101 Date 10/11	<b>The Recyclery</b> San Jose 101 DOON LANDING ROAD SAN JOSE, CA	SITE CIRCULATION PLAN DATE 10/11	<b>Beman &amp; Shultz Architects</b> 2000 Zeller Park Drive San Jose, California 95128 408.737.0100	REVISIONS NO. DATE BY
				1 2 3

**Fact Sheet #6  
The Recyclery at Newby Island  
San Jose, California**

**TYPE OF FACILITY:**

The Recyclery at Newby Island (Facility) is an 80,000 square foot materials recovery facility owned and operated by Browning Ferris Industries. The permitted Facility began operation in 1991, and includes both a manual sorting system and a semi-automated sorting system. The Facility processes both commingled (mixed) and source separated loads from residential and commercial recycling programs. The Facility also diverts loads of clean wood waste to other parts of the site to be processed and sold as Pro-Chip Mulch or wood fuel.

**FACILITY CAPACITY:**

The Facility is permitted to process a maximum of 1,600 tons per day. The Facility is currently processing approximately 1,000 tons per day.

**ESTMATED DIVERSION RATE:**

The Facility is currently diverting 90% (approximately 900 tons per day) of the material received for processing.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County and portions of Alameda, Contra Costa and San Mateo counties. The Facility processes curbside and commercial recyclables for several jurisdictions in Santa Clara County. The buy-back and public education center is open to the general public.

**FACILITY LOCATION:**


The Facility is adjacent to the Newby Island Landfill and is located at 1601 Dixon Landing Road in north San Jose, just west of Highway 880, near the southeastern end of the San Francisco Bay, (see the attached map).

REFERENCE:  
U.S.G.S. 7.5 Minute Series (Topographic),  
California-Gilroy Quadrangle.

0 1000 2000 4000  
SCALE IN FEET



**Site Location Map**



**Harding Lawson Associates**  
Engineering and  
Environmental Services

**Site Location Map**  
Report of Station Information  
San Martin Transfer Station  
Santa Clara County, California

PLATE  
**1**

DRAWN	JOB NUMBER	APPROVED	DATE	REVISED DATE
RPS	21371.2	<i>KML</i>	11/92	

**Fact Sheet #7**  
**San Martin Transfer and Recycling Station**  
**San Martin, California**

**TYPE OF FACILITY:**

The San Martin Transfer and Recycling Station (Facility) is owned and operated by Recology South Valley. The permitted 8-acre Facility began operations in 1968 along with the San Martin Landfill, and continued to operate after the landfill closed in 1971. The Facility accepts residential and commercial refuse, recyclables, organics, inerts and construction and demolition debris. Used motor oil and home-generated sharps are accepted from the public. Oil is limited to five gallons per container and 15 gallons per delivery. All materials are accepted through the scalehouse. The Facility salvages recyclable materials from the incoming waste stream. Wastes are handled separately from source separated recyclables and organics. Wastes are loaded into transfer trailers and hauled to a permitted solid waste disposal facility. Recyclables and organics are hauled to alternative processing or composting facilities.

**FACILITY CAPACITY:**

The facility is permitted to process a maximum of 500 tons of solid waste per day. The facility has no permit limits on the quantity of recyclable (curbside, inert, organics, cardboard, etc.) materials processed. The Facility currently processes approximately 250 tons of material per day. This facility is proposed to be closed in 2013 and will be replaced by the Pacheco Pass Transfer Station.

**ESTIMATED DIVERSION RATE:**


The Facility currently diverts over 50% of the incoming material each day. Non-recyclable materials are transferred to a permitted disposal site.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County. The Facility primarily serves the cities of Gilroy and Morgan Hill, the community of San Martin, other unincorporated areas of southern Santa Clara County and portions of northern San Benito County.

**FACILITY LOCATION:**

The Facility is located at 14070 Llagas Avenue, in the unincorporated community of San Martin in southern Santa Clara County (see attached map).



LOCATION MAP

DRAWN BY: JA DATE: CHECK'D BY: DATE:	<b>SMaRT STATION FACILITY</b> LOCATION MAP	APPROVED BY: _____ PE NO. _____ DATE: _____
SCALE: NONE	<b>City of Palo Alto</b>	DRAWING NO.

**Fact Sheet #8**  
**The Sunnyvale Materials Recovery and Transfer Station**  
**Sunnyvale, California**

**TYPE OF FACILITY:**

The Cities of Palo Alto and Mountain View are partners with the City of Sunnyvale for the development and operation of the Sunnyvale Materials Recovery and Transfer (SMaRT) Station (Facility). Sunnyvale managed the design and construction, and oversees the operation of the Facility. Palo Alto and Mountain View pay a proportionate share of the construction and operating costs based on the amount of municipal solid waste delivered to the Facility by the cities designated haulers. Completed in 1993, the permitted Facility is being used by the three cities to meet the state mandated goal of 50% waste reduction by the year 2000. When in full operation (scheduled for 1994), the Facility's primary function will be as a materials recovery facility. The Facility will receive and process curbside recyclables from the cities of Sunnyvale and Mountain View and will include a buyback recycling center. The Facility will also receive and process loads of municipal solid waste and recover materials from the incoming waste stream for the three participating cities. Recovered materials will be sent to brokers and markets which will use them for compacted, loaded, and hauled 27 miles south to the Kirby Canyon Recycling and Disposal Facility in south San Jose.

**FACILITY CAPACITY:**

The facility is permitted to process a maximum of 1500 tons of material per day. The facility currently processes approximately 900 tons of material per day. Allocation quantities for delivery of waste to the Facility are shown in Exhibit A.

**ESTIMATED DIVERSION RATE:**

Based on the terms of the agreement between the City of Sunnyvale and the Facility operator, the guaranteed diversion rate for the Facility is 25%. However, this guarantee is subject to adjustment based on the quantities of recyclable materials present in the municipal solid waste delivered to the Facility.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County. The Facility primarily serves the cities of Sunnyvale, Palo Alto and Mountain View.

**FACILITY LOCATION:**

The Facility is located in Santa Clara County, on City of Sunnyvale-owned property, northeast of the intersection of Caribbean Drive and Borregas Avenue, adjacent to the Sunnyvale Landfill, the Sunnyvale Water Quality Control Plant and the San Francisco Bay (see attached map).

SUNNYVALE MATERIAL RECOVER AND TRANSFER STATION


EXHIBIT A

Annual City Minimum Tonnage Commitment

YEAR	Sunnyvale	Mountain View	Palo Alto	TOTAL
1993*	72,465	39,403	26,011	137,879
1994	140,361	66,957	52,207	259,525
1995	135,7(X)	67,469	52,475	255,644
1996	132,873	68,277	50,949	252,099
1997	129,925	69,096	49,386	248,407
1998	126,922	69,926	47,787	244,635
1999	123,864	47,196	46,151	217,210
2000**	60,374	23,873	22,239	106,486
<b>TOTAL</b>	<b>922,484</b>	<b>452,196</b>	<b>347,205</b>	<b>1,721,885</b>

\* Assumes deliveries begin July 1, 1993

\*\* Assumes deliveries end June 30, 2000



**ZANKER**

Road Landfill

Zanker Road Resource Management, Ltd.

Owens-Corning Disposal Site  
 Zanker Road Resource Management, Ltd.  
 San Jose, California

Figure 1: Vicinity Map

**Fact Sheet #9**  
**Zanker Road Class III Landfill**  
**San Jose, California**

**TYPE OF FACILITY:**

The Zanker Road Class III Landfill (Facility) began operations in 1985 on a site formerly known as the Nine-Par Disposal Site (from 1934-1977). The 70-acre Facility (46 acres permitted for landfilling) is owned and operated by Zanker Road Resource Management, Ltd. The Facility is permitted to accept non-hazardous and non-putrescible solid wastes for processing. These wastes consist mainly of construction and demolition debris, (such as soil, asphalt, concrete, rebar and wood waste) yardwaste, metals, glass, plastic, and paper. The primary activities conducted at the Facility involve extensive resource recovery and recycling. Currently, there are five recycling operations that take place at the Facility: (1) sorting, splitting, chipping, screening, composting, stockpiling, and resale of wood waste; (2) separating, crushing, stockpiling, and resale of concrete waste; (3) hand separating recyclable materials from the incoming waste stream; (4) grinding and resale of wallboard waste (gypsum); (5) processing, screening, composting, and resale of yard waste compost products. The residual solid waste after processing is landfilled on site.

**FACILITY CAPACITY:**

The facility is permitted to landfill a maximum of 350 tons of waste per day. In 2002, an average of approximately 40 tons of waste was landfilled each day.

**ESTIMATED DIVERSION RATE:**

In 2002, the Facility received an average of approximately 800 tons per day for processing, and approximately 94% of the material was diverted from disposal.

**JURISDICTIONS SERVED:**

The Facility serves all of Santa Clara County and all neighboring counties.

**FACILITY LOCATION:**

The Facility is located at 705 Los Esteros Road in north San Jose off of Highway 237, near the southeastern end of the San Francisco Bay (see the attached map).

**Fact Sheet #10**  
**Dunne Ranch Composting Facility**

Deleted with the Fourth Amendment  
December 1999




EXHIBIT PREPARATION BY: BELLECCI & ASSOCIATES, INC.

Z-BEST COMPOSTING FACILITY

VICINITY MAP

SANTA CLARA COUNTY

CALIFORNIA

**Fact Sheet #11  
Z-Best Composting Facility  
Gilroy, California**

**TYPE OF FACILITY:**

The proposed Z-Best Composting Facility (Facility) is a proposed green waste composting facility that will be owned and operated by Zanker Road Resource Management, Ltd. The operators are currently seeking permits from the County of Santa Clara Department of Planning and Development, the County of Santa Clara Department of Environmental Health, the California Integrated Waste Management Board, the Central Coast Regional Water Quality Control Board, and the Bay Area Air Quality Management District. The operators expect to begin operations in the Fall of 1997. The 70-acre Facility is situated on a 157-acre parcel. The Facility will accept source-separated green waste, agricultural by-products, and other permitted organic materials from municipal collection programs, licensed contractors, and local agricultural operations. The Facility will not be open to the general public. Materials received at the Facility will be processed (screened or ground) and composted using an aerated windrow method. Finished compost will be cured, screened, temporarily stored on site, and transported to market as needed.

**FACILITY CAPACITY:**

The facility will have an estimated maximum processing capacity of 500 tons per day and is anticipated to accept an average of 200 tons per day.

**ESTIMATED DIVERSION RATE:**

The Facility will receive only materials that can be composted and therefore will have nearly a 100 percent diversion rate. Anticipated annual diversion would be an estimated 52,800 tons per year (based on 200 tons per day).

**JURISDICTIONS SERVED:**


The Facility would serve all of Santa Clara County as well as the surrounding south San Francisco Bay Area.

**FACILITY LOCATION:**

The Facility is located on the south side of Highway 25 at its intersection with Bolsa Road, which is between the cities of Gilroy and Hollister (see the attached map).

VICINITY MAP

EZTR-AAA.FH5, 03/20/97.



**Fact Sheet #12  
GreenWaste Recovery Facility  
San Jose, California**

**TYPE OF FACILITY:**

The proposed GreenWaste Recovery Facility (Facility) is owned by GreenWaste Recover, Incorporated. The Facility, which is approximately 6 acres in size, began operation in 1995 under a Conditional Use Permit from the City of San Jose. The Facility's primary function will be to recover recyclable materials from the waste stream for further processing and marketing. The Facility will operate a curbside recyclables processing operation, a yard waste transfer operation, and a debris box sorting and recycling operation. All sorting operations will be conducted inside a 40,250 square foot building. Materials which are sorted for recycling will be shipped to other recycling operations for further processing and marketing. The remaining waste will be shipped to permitted landfills for disposal. The Facility will also include the offices, collection vehicle parking, and maintenance facilities of GreenWaste Recovery and its associated businesses.

**FACILITY CAPACITY:**

The facility will be permitted to accept a maximum processing of 934 tons of compostable waste per day, with a weekly maximum of 4,200 tons. The Facility will be permitted to allow any combination of the following waste categories: curbside recyclables, debris box recycling, yard waste, commercial recyclables, and pre- and post-consumer food wastes from commercial, industrial, and residential sources.

**ESTIMATED DIVERSION RATE:**

The anticipated diversion rate for the Facility is approximately 84%.

**JURISDICTIONS SERVED:**

The Facility will serve all of Santa Clara County, northern San Benito County, and southern San Mateo County.


**FACILITY LOCATION:**

The Facility is located at 625 Charles Street, in San Jose. Charles Street can be reached by Old Oakland Road, east of Highway 101, or by Commercial Street, just south of Highway 880 interchange (see the attached map).

**Fact Sheet #13**  
**ComCare Farms Composting Facility**

Deleted with the Eighth Amendment  
February 2010

Project Location Map



**Fact Sheet #14  
South Valley Organics Composting Facility  
at Recology Pacheco Pass,  
Santa Clara County, California**

**TYPE OF FACILITY:**

The South Valley Organics Composting Facility is owned and operated by Recology Pacheco Pass. The Facility has received an Conditional Use Permit and Architectural Site Approval from the County of Santa Clara Department of Planning, a Full Compost Facility Permit (SWFP) from the County of Santa Clara Department of Environmental Health, a Waiver of Waste Discharge Requirements from the Central Coast Regional Water Quality Control Board, and a Permit to Operate from the Bay Area Air Quality Management District. The Facility accepts green waste, food waste, agricultural waste, and manure from Recology South Valley, and from other commercial haulers in the region. At the Facility, the material is actively composted using either windrow or in-vessel technology, prepared for market, and stored until delivered to markets. Finished product can be used on the site as a topsoil amendment for site revegetation and landfill closure.

**FACILITY CAPACITY:**

The Facility is designed to accommodate 450 tons average and 750 tons peak daily feedstock, or 117,000 tons annually.

**ESTIMATED DIVERSION:**


The anticipated diversion rate for the material received at the facility is 100%.

**JURISDICTIONS SERVED:**

The Facility serves jurisdictions within Santa Clara, San Benito, and other Bay Area Counties.

**LOCATION:**

The Facility is located at 3675 Pacheco Pass Road, in the southern portion of unincorporated Santa Clara County, and is within the boundaries of the Recology Pacheco Pass facility (see the attached map).



VICINITY MAP

Butterick Enterprises Recyclery  
San Jose, California

**Fact Sheet #15  
Butterick Enterprises Recyclery  
San Jose, California**

**TYPE OF FACILITY:**

The proposed Butterick Enterprises Recyclery (Facility) is owned by Butterick Enterprises. The Facility, which is 1.87 acres in size, began operation in 1989 as a materials recovery and transfer facility. A Conditional Use Permit for the Facility was issued in January 2000 by the City of San Jose. The Facility's primary function will be to recover recyclable materials from the waste stream for further processing and marketing. All sorting operations will take place outside. Materials sorted for recycling will be shipped to other recycling operations for further processing and marketing. The remaining waste will be shipped to permitted landfills for disposal. The Facility will also include the offices, collection vehicle parking, bin storage, and maintenance facilities for the operation.

**FACILITY CAPACITY:**

The Facility will be permitted to accept a maximum of 25,000 tons per year, with a monthly maximum of 3,100 tons. The Facility will be permitted to allow any combination of the following waste categories: debris box recycling, commercial, industrial, and residential recyclables. The site is not permitted to accept hazardous material, green waste, brush, garbage, or food waste.

**ESTIMATED DIVERSION:**

The anticipated diversion rate for the Facility is approximately 70%.

**JURISDICTIONS SERVED:**

The Facility will serve all of Santa Clara County.

**LOCATION:**

The Facility is located at 505 Burke Street, San Jose. Burke Street can be reached off Tully Road from Highway 101 (see the attached map).




FIGURE 1

 <p>(909) 860-7777</p> <p><b>BRYAN A. STIRRAT &amp; ASSOCIATES</b>          CIVIL AND ENVIRONMENTAL ENGINEERS          1380 VALLEY VISTA DRIVE DIAMOND BAR, CA 91765</p>	<p>PREMIER RECYCLING FACILITY</p>	<p>JOB NO. 2000.019-200</p>
	<p><b>VICINITY MAP</b></p>	<p>DATE 2-2000</p> <p>DRAWN BY J.J.G</p> <p>FILE NAME 02082DB.</p>

**Fact Sheet #16**  
**Premier Recycling Facility**  
**San Jose, California**

**TYPE OF FACILITY:**

The proposed Premier Recycling Facility (Facility) is owned by Premier Recycling and is a proposed large volume transfer/processing facility. The Facility, which is 1.44 acres in size, began operation in 1997 as a construction/demolition materials recycler. The Facility's primary function will be to recover recyclable materials from construction/demolition activities for further processing and marketing. All sorting operations will take place outside. Sorted recyclable materials will be shipped to other recycling operations for further processing and marketing. The residual waste will be transported to a permitted landfill for disposal. The Facility will also include an office, transfer vehicle parking, and maintenance facilities for the operation.

**FACILITY CAPACITY:**

The Facility will accept approximately 300 tons per day / 93,000 tons per year, or as specified in the most recently issued Solid Waste Facilities Permit (SWFP). The Facility will accept various recyclables including cardboard, scrap metal, wood, sheetrock, concrete, and other non-putrescible commercial/ demolition waste. The maximum inflow rate and the type and quantities of materials and the facility operations will be governed by the SWFP issued by the City of San Jose Code Enforcement, Local Enforcement Agency Program.

**ESTIMATED DIVERSION:**

The anticipated diversion rate for the Facility is approximately 80%.

**JURISDICTIONS SERVED:**


The Facility will serve the greater San Jose Metropolitan Area, all of Santa Clara County, and adjoining counties.

**LOCATION:**

The Facility is located at 260 Leo Avenue, San Jose. Access to the facility is from Leo Avenue (see the attached map).

**Fact Sheet #17**  
**Environmental Management Systems Facility**

Deleted with the Seventh Amendment  
August 2009



Vicinity Map

California Waste Solutions  
San Jose, California

**Fact Sheet #18  
California Waste Solutions Recycling & Transfer Station  
San Jose, California**

**TYPE OF FACILITY:** Large Volume Transfer/Processing Facility

The California Waste Solutions Recycling & Transfer Station is operated by California Waste Solutions and owned by Duong Family Investments. The facility, which is 3.57 acres, began operations in August 2002 as a recycling center. A Conditional Use Permit was issued in March 2002 by the City of San Jose to operate a “curbside recycling processing and transfer facility.” All sorting operations occur within the building. Sorted materials are sent for processing and marketing at other locations. Residual solid waste from the operation will be sent to an authorized facility. Non-hazardous residual wastes are sent for disposal at permitted landfills. Hazardous and other prohibited wastes will be sent to approved recycling, treatment, or disposal facilities. Other activities at this site include administrative offices and employee parking.

**FACILITY CAPACITY:**

The Facility’s design capacity for the intended material stream of commingled recyclables is 530 tons per day. Under terms of its Conditional Use Permit, it is permitted to accept a maximum of 110,000 tons per year.

**ESTIMATED DIVERSION:**


The estimated diversion rate for the Facility is approximately seventy (70%) to ninety (90%) percent.

**JURISDICTIONS SERVED:**

The City of San José. Subject to the tonnage limits above, as they may be amended, the facility may serve all of the jurisdictions in Santa Clara County.

**LOCATION:**

The Facility is located at 1005 Timothy Drive, San Jose, California 95133. Access to the facility is from Yard Court.



**Fact Sheet #19  
Pacific Coast Recycling  
Gilroy, California**

**TYPE OF FACILITY:**

The Pacific Coast Recycling Facility (Facility) is a recycling processing and transfer facility receiving commingled recyclables. The Facility is located on 6.1 acres at 5895 Obata Way, Gilroy. The business will operate from 7:00 a.m. – 5:00 p.m. six days per week. The Facility recycles construction waste; i.e. roofing, wall, flooring, plumbing, electrical, asphalt, concrete and masonry materials are all typical. This operation will also receive organic garden and landscape wastes. The Facility does not receive food, food packaging or food service waste nor will it handle hazardous materials (except Freon).

**FACILITY CAPACITY:**

The Facility is permitted to accept no more than 100 tons per day.

**ESTIMATED DIVERSION:**

Approximately 90% of all incoming materials is recycled.

**JURISDICTIONS SERVED:**

This Facility will serve the Santa Clara County and small percentage from San Benito County.

**LOCATION:**

The Facility is located at 5895 Obata Way, Gilroy, CA 95020. Access to the facility is off Obata Way with ingress/egress provided by two driveway entrances (see the attached map).



**Fact Sheet #20  
Pacheco Pass Transfer Station  
Santa Clara County, California**

**TYPE OF FACILITY:**

The proposed Pacheco Pass Transfer Station is owned and operated by Recology Pacheco Pass (RPP). RPP is currently in the process to obtain a Use Permit from the County of Santa Clara, which is anticipated to be issued in 2011. The facility will accept municipal solid waste and mixed recyclables from Recology South Valley collection vehicles and other commercial haulers. Municipal solid waste and mixed recyclables is loaded into transfer trailers and transported to nearby vendors for processing or to permitted landfill for disposal. This facility will replace the San Martin Transfer Station, which will close in 2013.

**FACILITY CAPACITY:**

The facility is designed to accommodate 500 tons per day average, and 1,000 tons per day peak of municipal solid waste and mixed recyclables.

**ESTIMATED DIVERSION:**

Only transfer operations will occur at the facility. No sorting or processing is performed. The anticipated diversion rate at this facility is 0%.

**JURISDICTIONS SERVED:**

This facility primarily serves the Cities of Gilroy and Morgan Hill and the community of San Martin, other unincorporated areas of southern Santa Clara County.


**LOCATION:**

The Facility is located at 3675 Pacheco Pass Highway, in the southern portion of unincorporated Santa Clara County, and within the permitted boundaries of Recology Pacheco Pass (see the attached map).

# Stanford Recycling Center and Direct Transfer Facility

339 Bonair Siding, Stanford, California 94305

## Vicinity Map



**Fact Sheet #21**  
**Stanford Recycling Center and Direct Transfer Facility**  
**Stanford, California**

**TYPE OF FACILITY:**

The Stanford Recycling Center and Direct Transfer Facility (Facility) is owned and operated by Peninsula Sanitary Service, Inc. (PSSI). The Stanford Recycling Center was established in 1976 with the goal of diverting recyclable materials from landfill. Peninsula Sanitary Service has been the university's solid waste hauler since 1943. The company provides a full array of refuse, yard waste and food waste, recyclables, and construction and demolition services to the campus community including academic and operations buildings, student housing and faculty and staff housing. The Facility currently receives source-separated and mixed recyclables through drop-off and on-campus collection routes. The mixed recyclables are separated through mechanical and manual means utilizing a mechanized processing line at the Facility. Materials accepted include glass jars and bottles, aluminum and tin cans, scrap aluminum, corrugated cardboard, newspapers, magazines, high-grade and mixed paper, telephone books, and waste products of assorted plastic resins.

The Facility proposes to operate a Direct Transfer Facilities (DTF), which can be permitted for up to 150 tons per day (TPD) with a Registration Solid Waste Facility Permit (SWFP). The DTF would handle commingled recyclables, green waste, commingled green waste and food waste, mixed construction and demolition (C&D) debris and/or municipal solid waste (MSW) which will be transferred directly from collection vehicles into direct transfer trailers to maximize the efficiency of transporting materials to off-site processing facilities for the commingled recyclables and mixed C&D, to off-site composting facility for the comingled green waste and food waste, and to a landfill for the MSW. This will garner additional diversion of materials by processing recyclables, mixed C&D, and commingled green waste and food waste at facilities utilizing higher-technology equipment, and reduce the overall diesel use for the operations, minimizing emissions and ultimately the size of the Facility's carbon footprint.

**FACILITY CAPACITY:**

Approximately 60 tons per day of recyclables were accepted for processing at the Facility during 2007. In addition to the recyclables collection and processing, the Facility proposes to transfer recyclables, commingled green waste and food waste, mixed C&D and MSW at the DTF, the processing and transfer operations have an estimated annual operation capacity of approximately 22,000 tons, with a peak loading capacity of 150 tons per day for the DTF operations.

**ESTIMATED DIVERSION RATE:**


In 2007, total waste generated at the university was 22,013 tons. Based on these figures, the 2007 diversion rate for the facility was approximately 60% of the total waste stream.

**JURISDICTIONS SERVED:**

The Facility serves the Incorporated and Unincorporated Stanford University Lands in the County of Santa Clara and San Mateo. The Facility is primarily used by students, faculty, and staff at the Stanford University campus.

**FACILITY LOCATION:**

The Facility is located in Santa Clara County within the Stanford University Community Plan Area at 339 Bonair Siding, Stanford. (see the attached map).



	<b>EDGAR &amp; ASSOCIATES, INC.</b> 1822 21ST STREET SACRAMENTO, CA 95814 PHONE: (916) 750-1200 FAX: (916) 750-1218		<b>LOCATON MAP</b>  FOR <b>GREENTeAM MRF</b>	SHEET <b>1</b>
	1" = 500' JUNE 11, 2009	JOB NUMBER: 170.14.20.01 FILENAME: 170.14.20.01.DWG		

**Fact Sheet #22  
GreenTeam of San Jose Material Recovery Facility and Transfer Station  
San Jose, California**

**TYPE OF FACILITY:**

The GreenTeam of San Jose Material Recovery Facility and Transfer Station (GTSJ-MRF) is a wholly-owned subsidiary of Waste Connections of California, Inc. The GTSJ-MRF primarily provides recyclables processing and storage, and solid waste transfer at this site. With the Solid Waste Facility Permit, the GTSJ-MRF plans to harmonize the hours of operations, clarify the outside storage of recyclables – including the bales, bulky materials, and single stream material, and provide appropriate odor and dust mitigation plans for the site and add screening.

**FACILITY CAPACITY:**

The facility is designed to accommodate 500 tons per day average of commingled recyclables, and 210 vehicles trips per day.

**ESTIMATED DIVERSION:**


Processing and transfer will occur on site at the facility. The anticipated diversion rate at this facility will be 90%.

**JURISDICTIONS SERVED:**

This facility primarily serves the Cities of San Jose.

**LOCATION:**

The Facility is located at 575 Charles Street, San Jose, CA 95112, in the northern portion of the city, and within the permitted boundaries of the Waste Connections GreenTeam of San Jose Material Recovery Facility and Transfer Station (GTSJ-MRF).



APPROX SCALE

NOT TO SCALE



SOURCE  
2008 Rand McNally

DATE  
04/01/09

ADDRESS  
2765 Lafayette St., Santa Clara, CA 95050

## SITE LOCATION MAP

GreenWaste Material Processing and  
Transfer Station

FIGURE

# 1

**Fact Sheet #23**  
**GreenWaste Material Processing and Transfer Station**  
**Santa Clara, California**

**TYPE OF FACILITY:**

GreenWaste Recovery, Inc. (GreenWaste) is proposing to operate a material processing and transfer facility on 1.87 acres of a 6.44 acre parcel in the City of Santa Clara. Currently GreenWaste uses the site for parking and servicing collection vehicles. The proposed GreenWaste Material Processing and Transfer Station (GWTS) will be operated by GreenWaste on leased property owned by a private party. The GWTS will process and transfer green and compostable materials. The facility's primary function will be to process green and compostable materials prior to being transferred to a compost facility. Green materials such as yard trimmings and wood waste will be processed through size reduction equipment prior to transfer. Compostable materials such as source separated food material will be transferred directly with minimal sorting to remove contaminants and other recyclables. GreenWaste has been processing green and compostable materials for over 10 years and currently owns and operates a similar facility in the City of San Jose.

**FACILITY CAPACITY:**

A maximum of 1,500 tons per day of green materials (approximately 75-80% by weight) and compostable materials (approximately 20-25% by weight) is proposed.

**ESTIMATED DIVERSION:**

GreenWaste is estimating 99% diversion of green materials and compostable materials.

**JURISDICTIONS SERVED:**

The GreenWaste Material Processing and Transfer Station will service the Santa Clara County and surrounding counties. The facility will not be open to the general public.

**LOCATION:**

The Facility is located in the City of Santa Clara at 2765 Lafayette Street. Refer to attached Site Location Map.



**Fact Sheet #24  
Recology Silicon Valley Processing and Transfer Facility  
San Jose, California**

**TYPE OF FACILITY:**

The Recology Silicon Valley Processing and Transfer Facility is an existing medium-volume transfer station that is permitted to receive up to 99 tons per day of mixed waste materials including organic material, residential and commercial refuse and inert material. It is proposed to expand the facility to receive and process recyclable, organic and waste materials from the City of San Jose commercial recycling program and other sources.

**FACILITY CAPACITY:**

The facility is currently permitted to receive up to 99 tons per day. The facility expansion will be designed to handle up to 600 tons per day of residential and commercial recyclable, organic and waste materials.

**ESTIMATED DIVERSION:**


Processing and transfer will occur at the facility. The estimated overall diversion rate is above 60 percent. Recovered materials will be transported from the facility for further processing or to markets. Residual materials will be transported to a permitted disposal site.

**JURISDICTIONS SERVED:**

The facility will serve San Jose and other South Bay cities.

**LOCATION:**

The facility is located at 1675 Rogers Avenue, San Jose. Refer to attached Site Location Map.




Adapted from USGS Map, California 7.5 Minute Series, Milpitas, CA (Photo revised 1980) Quadrangle.

**SCS ENGINEERS**

6601 Koll Center Parkway,  
Suite 140  
Pleasanton, CA 94566  
Ph: (925) 426-0080  
Fax: (925) 426-0707

**FIGURE 1**  
**SITE LOCATION**  
**9 PAR LANDFILL SITE**  
**SAN JOSE, CALIFORNIA**

PROJECT NO: 01206142.00		CHECKED BY: JJM
DESIGNED BY: HLG	SCALE: NTS	APPROVED BY: JJM
DRAWN BY: HLG	DATE: 3/07	FILE:



BASE TOPOGRAPHY - 2004 (CITY OF SAN JOSE)

**SCS ENGINEERS**  
ENVIRONMENTAL CONSULTANTS

8601 KOLL CENTER PARKWAY, SUITE 140  
PLEASANTON, CALIFORNIA 94688  
PHONE: (925) 428-0080 FAX: (925) 428-0707

**SITE VICINITY MAP**

**9 PAR LANDFILL SITE**  
**SAN JOSE, CALIFORNIA**

SCALE: AS SHOWN

PROJECT NO. 01208142.00

DATE: 4-6-07

FIGURE NO.

**2**

**Fact Sheet #25**  
**Zero Waste Energy Development Company Anaerobic Digestion Facility**  
**San Jose, California**

**TYPE OF FACILITY:**

Zero Waste Energy Development Company (Zero Waste), a joint venture between GreenWaste Recovery, Inc. and its sister company Zanker Road Resource Management (Zanker), is developing the first of its kind in the nation dry fermentation anaerobic digestion facility. Although anaerobic digestion is common in the United States, all the existing processes employ wet feedstock. While the dry-fermentation technology that will be deployed has been commercially demonstrated in Europe for agricultural feedstocks and some MSW feedstocks, there are currently no dry-fermentation anaerobic digestion projects operating in the United States.

**FACILITY CAPACITY:**

This 150,000 tons per year facility will be developed in three phases; each of the three phases will be capable of processing 50,000 tons per year of organic materials.

**FEEDSTOCK:**

The facility will process and recover energy from source separated food waste and the organic fraction remaining after materials including municipal solid waste (MSW) are processed at GreenWaste's MRF and create two products: a biogas containing methane and compost. We anticipate phase I of the project will produce 13 million kilowatt hours of electricity per year – enough to power approximately 1,300 homes.

**ESTIMATED DIVERSION:**


GreenWaste is estimating 80% diversion of green materials and compostable materials.

**JURISDICTIONS SERVED:**

This facility has been designed to accommodate the current and growing stream of organic waste generated by San Jose and nearby municipalities.

**LOCATION:**

The proposed site for this facility is located at the former Nine Par landfill at 2100 Los Esteros Road, in the City of San Jose, adjacent to the existing Zanker processing facilities. Refer to attached Site Location Map.



650 Kings Row

File No: SP09-026

District: 4

Quad No: 51



05/08/2009

Noticing Radius: 500 feet

**Fact Sheet #26  
Green Earth Management LLC Kings Row Recycling Facility  
San Jose, California**

**TYPE OF FACILITY:**

The Green Earth Management LLC Kings Row Recycling Facility is an existing Chipping and Grinding Operation on 0.91 acres of leased property permitted to handle up to 199 tons per day of green materials. Green Earth Management LLC. is planning to expand their material processing and transfer facility in the future. The Kings Row Recycling Facility currently chips and grinds green material for transfer to biomass energy facilities. The planned expanded facility's primary function will be to process green and compostable materials prior to being transferred to compost or energy facilities.

**FACILITY CAPACITY:**

The facility is currently permitted to handle up to 199 tons per day. A maximum of 600 tons per day of green materials (approximately 75-80% by weight) and compostable materials (approximately 20-25% by weight) is planned in the future.

**ESTIMATED DIVERSION:**

Kings Row Recycling Facility is estimating 99% diversion of green materials and compostable materials.

**JURISDICTIONS SERVED:**



The Kings Row Recycling Facility will service Santa Clara County and surrounding counties. The facility will be open to the public.

**LOCATION:**

The facility is located in the Enterprise Zone of the City of San Jose at 650 Kings Row. Refer to attached site location map.

**APN#:**

23730005 and 23730006



**Valley Recycling Site by Parcels**  
 1615 B South 7th Street  
 San Jose, CA 95112

Valley Recycling Operation is on Parcel 20 (PCL1)  
 A portion of Parcel 18 (PCL2) and 19 (PCL3) is used for Truck Parking and Container Storage  
 Areas are highlighted in yellow

**BOOK  
455**

TRA DET. MAP 118  
 LAWRENCE E. STONE — ASSESSOR  
 Cadastral map for assessment purposes only.  
 Compiled under R. & T. Code, Sec. 327.  
 Effective Roll Year 2008-2009

**Fact Sheet #27**  
**Environmental Resources Recovery Inc. (Valley Recycling)**  
**San Jose, California**

**TYPE OF FACILITY:**

Environmental Resource Recovery Inc. (Valley Recycling) is currently permitted as a Medium Volume Construction Demolition Debris Facility. Valley Recycling has been in business since 1986 on property leased from a private party. This facility is currently operating under state and local limits of 175 tons per day. This facility is currently seeking to move a higher state permit “Tier” to implement future plans to process and increase tonnage as a fully permitted solid waste facility, within allowable limits of state and local permit entitlements. The existing medium volume C&D facility has storage bunkers, assorted sizes of dumpster and parking for the roll-off vehicles, and related trucks with compactor-loads.

**FACILITY CAPACITY:**

A maximum of 175 tons per day of Construction, Demolition and assorted Debris.

**ESTIMATED DIVERSION:**


The existing facility recycles less than 5% of the volume received at this time. As new state and local permit entitlements are approved, future operations may increase processing and recycling levels. Their stated goal in the future is to maximize the diversion that may allow up to or in excess of 75% diversion. They are in the early stages with LEA to go to the next “Tier” up and at this time it is uncertain what will be required.

**JURISDICTIONS SERVED:**

Valley Recycling services the Bay Area and will be looking to expand in the future.

**LOCATION:**

The facility is located at 1615 B South 7<sup>th</sup> Street in San Jose. Site Map Attached.



**Smurfit-Stone Recycling San Jose Facility Location Map**  
205 East Alma Avenue, San Jose, CA 95112-5902

**Fact Sheet #28  
Smurfit-Stone Recycling San Jose Facility  
San Jose, California**

**TYPE OF FACILITY:**

The Smurfit-Stone Recycling San Jose Facility is a recycling processing and transfer facility receiving commingled and source separated recyclables operated by Smurfit-Stone Recycling and Waste Services. The facility, which is 5.17 acres, began operations in 1982 as a recycling center. This facility is seeking a permit as a solid waste processing and transfer facility in anticipation of incoming recyclables that could be in excess of the state mandated ten percent residual limit. All sorting operations occur within the building. Sorted materials are sent for processing and marketing at other locations. Residual wastes are sent for disposal at permitted landfills. Other activities at this site include: administrative offices and employee parking.

**FACILITY CAPACITY:**

The Facility's design capacity is 960 tons per day of recyclable commodities including but not limited to cardboard, paper, and beverage containers. Residual solid waste from the operation will be sent on to an authorized facility. Hazardous and other prohibited wastes will be sent to approved recycling, treatment, or disposal facilities.

**ESTIMATED DIVERSION:**


The anticipated diversion rate for the facility will be over 90 percent.

**JURISDICTIONS SERVED:**

The Facility will serve the City of San Jose and other jurisdictions in Santa Clara County.

**LOCATION:**

The facility is located at 205 East Alma Avenue in San Jose. Access to the facility is from East Alma Avenue. Site Map Attached.



	<p><b>Recology Pacheco Pass</b></p> <p><b>Construction and Demolition Debris Processing Facility</b></p> <p><b>3675 Pacheco Pass Hwy, Gilroy, California</b></p>
	<p><b>Site Location Map</b></p>

**Fact Sheet #29**  
**Recology Pacheco Pass Wood Processing Facility**  
**Santa Clara County, California**

**TYPE OF FACILITY:**

The proposed Facility is owned and operated by Recology Pacheco Pass (RPP). The Wood Processing Facility is planned for continued operation at the existing RPP Landfill after final closure of the landfill. After final closure of the landfill, the Facility will operate under a separate Solid Waste Facility Permit, as a Medium Volume Construction Demolition/Inert Debris Processing Facility. The facility was described in the Modification of the Conditional Use Permit by the County of Santa Clara in January of 2011. The facility, which is approximately 2.5 acres, processes a combination of wood and wood-related construction and demolition (C&D) debris accepted from Recology collection vehicles and other commercial haulers. The facility will use the scale, access roads, and supporting infrastructure of the two other facilities that will share other areas of the property, South Valley Organics (composting) and the Pacheco Pass Transfer Station (pending construction). All sorting operations will be completed using loaders and personnel by hand.

**FACILITY CAPACITY:**

The facility will be permitted to accept a maximum for processing of 175 tons per operating day. The inbound material may be of any combination of green material (stumps and logs), wood and wood-related C&D debris. The storage capacity on the 2.5 acre processing area is approximately 5,000 cubic yards.

**ESTIMATED DIVERSION:**

The Facility will divert a minimum of 60% of each load of incoming material.. Non-recyclable materials are transferred to a permitted disposal site.

**JURISDICTIONS SERVED:**

The facility primarily serves the Cities of Gilroy and Morgan Hill, the community of San Martin, and other unincorporated areas of southern Santa Clara County.

**LOCATION:**

The facility is located at 3675 Pacheco Pass Highway, in the southern portion of unincorporated Santa Clara County. It is within the current permitted boundaries of RPP Landfill but will not be directly over waste. (see attached map).

# VALLEY RECYCLING


## EAST 7TH STREET SPECIAL USE PERMIT DECEMBER 2013

### PROJECT TEAM


**OWNER:**  
 VALLEY RECYCLING  
 1615 S 7TH STREET  
 SAN JOSE, CA 95112  
 408-297-5382 (TEL)

**CIVIL ENGINEERS:**  
 BKF ENGINEERS  
 1650 TECHNOLOGY DRIVE, SUITE 650  
 SAN JOSE, CA 95110  
 408-487-9100 (TEL)

**LANDSCAPE ARCHITECTURE:**  
 HANSEN MCARDLE INC  
 3400 MT DIABLO BLVD, SUITE 209  
 LAFAYETTE, CA 94549  
 925-283-5520 (TEL)



VICINITY MAP  
 NOT TO SCALE



### SHEET INDEX

SHEET NO.	SHEET REFERENCE	DESCRIPTION
1	T-1	TITLE SHEET
2	A-1	MODULAR OFFICE ELEVATIONS
3	A-2	FENCE ELEVATIONS AND SECTIONS
4	A-3	LANDSCAPE PLAN
5	L-1	GRADING AND DRAINAGE PLAN
6	C-1	UTILITY PLAN
7	C-2	STORMWATER CONTROL PLAN
8	C-3	STORMWATER CONTROL PLAN
9	C-4	STORMWATER CONTROL PLAN DETAILS

DATE: 12/18/13 SHEET NO.: 01 OF 09 DRAWING NO.: T-1	<b>VALLEY RECYCLING</b> <b>SPECIAL USE PERMIT</b> <b>TITLE SHEET</b> SAN JOSE      SANTA CLARA COUNTY      CALIFORNIA	<b>BKF</b> ENGINEERS / SURVEYORS / PLANNERS 1850 TECHNOLOGY DRIVE SUITE 250 SAN JOSE, CA 95110 408-482-9100 (TEL) 408-482-9199 (FAX)	REGISTERED PROFESSIONAL ENGINEER C 050660 CIVIL 12/20/2013	<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="5">REVISIONS</th> </tr> <tr> <th>NO.</th> <th>DESCRIPTION</th> <th>BY</th> <th>DATE</th> <th>APP'VD</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS					NO.	DESCRIPTION	BY	DATE	APP'VD															
REVISIONS																													
NO.	DESCRIPTION	BY	DATE	APP'VD																									

**Fact Sheet #30  
Valley Recycling San Jose CDI Processing/Transfer Facility  
Santa Clara County, California**

**TYPE OF FACILITY:**

Medium Volume Direct Construction, Demolition Debris, and Inerts (CDI) Processing/Transfer Facility. Valley Recycling San Jose proposes to develop CDI operations on this property.

**FACILITY CAPACITY:**

174.9 Tons per day maximum volume of CDI material received, and open 362 days per year (closed Thanksgiving, Christmas, and New Year's)

**ESTIMATED DIVERSION:**


All clean source separated material type received will be segregated and delivered for reuse or recycling. All comingled CDI materials received will be sorted, processed, separated, and delivered to other CDI processing certified facilities, and permitted landfills. Material transferred from facility is anticipated to be delivered to facilities both within and outside of Santa Clara County (majority anticipated to be outside Santa Clara County) for recycling, reuse, processing of materials, and residue disposal. Diversion from landfilling of materials received is estimated to be in excess of 60%.

**JURISDICTIONS SERVED:**

This facility will be available to serve the City of San Jose, surrounding municipalities, and the unincorporated areas of Santa Clara County.

**LOCATION:**

The proposed site for this facility will be located on a vacated piece of railroad property adjacent to 1615-B South 7<sup>th</sup> Street, San Jose, CA 95112. Refer to attached Site Location drawing. (See attached map).



MISSION TRAIL FOOD MATERIAL PROCESSING OPERATIONS 1060 RICHARD AVENUE SANTA CLARA, CALIFORNIA		SCALE: 1" = 1850'
LOCATION MAP		
DATE: FEBRUARY 25, 2014	FIGURE 1	

**Fact Sheet #31  
Mission Trail Food Materials Transfer/Processing Operations  
Santa Clara, California**

**TYPE OF FACILITY:**

The Mission Trail Food Materials Transfer/Processing Operations (FMTPO) is owned and operated by Mission Trail Waste Systems (MT) and is located on approximately 0.9 acres at the existing Mission Trail Transfer Station.

The FMTPO is a transfer/processing facility handling compostable food materials, collected from restaurants and other regional food production operations, that are to be processed and transferred to a permitted facility for use as a compost feedstock, anaerobic digestion feedstock, or in the production of animal feed. The FMTPO uses sealed containers for the collection of food materials, where they are introduced into proprietary equipment for separation from contaminants. The enclosed processing system retains all liquids and food materials in a sealed tank which will be pumped into sealed trailers for transportation, with residual contaminants expelled into covered containers.

The FMTPO will garner additional diversion of food waste materials – in accordance with the Climate Action Plans approved by the City of Santa Clara other jurisdictions, by processing food waste into a usable feedstock commodity for composting, anaerobic digestion, or animal feed, minimizing landfill and transportation emissions and ultimately the size of the facility and community carbon footprints.

**FACILITY CAPACITY:**

The FMTPO is designed to handle up to 99 tons per day of food materials and approximately 30 vehicle trips per day.

**ESTMATED DIVERSION RATE:**

Processing and transfer will occur on site at the facility. The anticipated diversion rate at this facility will be 50%.

**JURISDICTIONS SERVED:**


The FMTPO serves primarily the City of Santa Clara and Unincorporated County of Santa Clara, in addition to other regional jurisdictions.

**FACILITY LOCATION:**

The Facility is located at 1060 Richard Avenue, Santa Clara, CA 95050 (see the attached map).



Address 1255 Yard Ct  
San Jose, CA 95133



**Fact Sheet #32  
ECO Box Recycling, Inc.  
San Jose, California**

**TYPE OF FACILITY:**

Medium Construction and Demolition/Inert Debris Processing Facilities ( $25 \text{ tpd} \leq x < 175 \text{ tpd}$ )

ECO Box Recycling San Jose proposes to operate a Registration Tier Permitted CDI Facility on this property.

**FACILITY CAPACITY:**

75 tons per day maximum volume of CDI material received

**ESTIMATED DIVERSION:**

All clean source separated material type received will be segregated and delivered for reuse or recycling. All comingled CDI materials received will be sorted, processed, separated, and delivered to other CDI processing certified facilities, and permitted landfills. Material transferred from facility is anticipated to be delivered to facilities both within and outside of Santa Clara County for recycling, reuse, processing of materials, and residue disposal. Diversion from landfilling of materials received is estimated to be in excess of 60%.

**JURISDICTIONS SERVED:**



This facility will be available to serve the City of San Jose, surrounding municipalities, and the unincorporated areas of Santa Clara County.

**LOCATION:**

The proposed site for this facility will be located 1255 Yard Court, San Jose, CA 95133. Refer to attached Site Location (see attached map).

# MAP OF LEO RECYCLE

215 Leo Ave  
San José, CA



Google  
Map data ©2016 Google

**Fact Sheet # 33**  
**Leo Recycle**  
**San José, California**

**TYPE OF FACILITY:**

Medium Construction and Demolition/Inert Debris Processing Facilities ( $25 \text{ tpd} \leq x < 175 \text{ tpd}$ )

Lam Hauling, Inc. (DBA: Leo Recycle) proposes to operate a Registration Tier Permitted CDI Facility on this property. The facility consists of one half (25,000 square feet, designated Suite 10) of the building located at 215 Leo Ave (50,000 square foot building). The second half of the building (Suite 20) is operating independently as a Recycling Center, as defined by CalRecycle. Both Suites have access and utilize the same entrances, exits, parking, roads, and scale.

Leo Recycle accepts Construction & Demolition debris, Inert debris, Green waste. Materials are inspected and weighed prior to receipt. Once accepted, materials are deposited into designated piles and/or sorted, before being transported to their appropriate processing facilities. Residual materials are transported to permitted landfills.

**FACILITY CAPACITY:**

175 tons per day maximum volume of CDI material received.

**ESTIMATED DIVERSION:**

All clean source separated material type received will be segregated and delivered for reuse or recycling. All co-mingled CDI materials received will be sorted, processed, separated, and delivered to other CDI processing certified facilities, and permitted landfills. Material transferred from facility is anticipated to be delivered to facilities both within and outside of Santa Clara County for recycling, reuse, processing of materials, and residue disposal -- including Merced County and Solano County. Diversion from landfilling of materials received is estimated to be in excess of 60%.

**JURISDICTIONS SERVED:**

This facility will be available to serve the City of San Jose, surrounding municipalities, and the unincorporated areas of Santa Clara County.

**LOCATION:**

The facility is located 215 Leo Ave, San Jose, CA 95112. It is zoned as Heavy Industrial and conforms to its surrounding urban pattern. See attached map.